


MCR-03 Fencing Additions

ITEM	QUAN.	UNIT	COST/UNIT	TOTAL
GENERAL CONDITIONS				
On-site field supervision	4	mh	125.00	500.00
Sub total Gen Conditions				500.00
Sub Contracted Work:				
1. Install 8' wrought iron fence with curved top	177	LF		37,112.00
2. Install 6' chainlink with 3 strand barb wire	532	lf		
3. 30' rolling gate	2	ea		
Total Subcontracted Work				37,112.00
General Contractor Work				
1. Concrete pedestal with metal track	4	ea		
GC Labor with burden (4 men crew)	6	hr	212.00	1,272.00
GC Matrl	1	ls		861.00
GC Equipment	3	hr	70.00	210.00
Operator	3	hr	47.00	184.00
GC Subtotal				2,527.00
GC markup for Subcontracted Work at 10%				3,711.20
GC markup for own work at 10%				252.70
GC TOTAL:				6,490.90
PROJECT SUBTOTAL w/o Tax				44,102.90
NMGRT @ 8.3125%				3,666.05
TOTAL WITH TAXES				47,768.95



GALLUP FENCE & CONSTRUCTION CO., INC.

1304 COUNTRY CLUB PLACE • GALLUP, NM 87301
WAREHOUSE 411 NORTH 3RD ST.

OFFICE PH: 505-863-3440

FAX: 505-722-3293

WAREHOUSE PH: 505-863-5148

Gallup Solid Waste

Post-it® Fax Note	7671	Date	# of pages ▶
To	<i>Murphy Bldg</i>	From	<i>L. CHURCH</i>
Co./Dept.		Co.	<i>GALLUP FENCE</i>
Phone #	<i>863-6274</i>	Phone #	<i>863-3440</i>
Fax #	<i>863-9447</i>	Fax #	<i>722-3293</i>

INSTAL S32 LINAL.
 Pt 6 Heavy C2
 fence with 2
 32" Rolling DO Gates
 3 strands BARB wire
 2 7/8 CORNER & Gate post
 1 7/8 line post. 1 5/8
 top rail #9 fabric.
 Plus 175 8' AmerStar
 Wrought Iron with
 West Curve top. 3/4 pickets
 3 Rail-

Total Amt. 37,112.